

# UNION ROAD VOLUNTEER FIRE DEPARTMENT, INC.

4060 UNION ROAD GASTONIA, N. C. 28056

To: Gaston County Fire Advisory Board

From: Chief Craig Huffstetler

All,

Union Road VFD is requesting the use of funds from our overage account. Our intention is to purchase a breathing air compressor for our station. We are currently in the process of spec'ing a new rescue pumper and this truck will not have a cascade system on it as our current one does. The compressor will be purchased and installed through Safe Air Systems. I have attached the specifications of the compressor along with the quote for the compressor and electrical work. The total cost of the compressor is \$39,505 and the required electrical work is \$1500. This item was presented to and approved by our Board of Directors on May 23<sup>rd</sup>. As it currently stands our overage amount is at \$90,655.62. Thank you for your time and consideration.

Craig Huffsteler Fire Chief Union Road VFD Urvfd5100@yahoo.com 980-522-1525

## QUOTE

#### M A Cowart Electric

Licensed and Insured

INVOICE # 1122 DATE: 5/20/19

riceisea and monea

**EXPIRATION DATE DATE** 

569 Crowders Creek Rd Gastonia, NC 28052 704-678-8728

TO Craig Huffstetler Union Road VFD 4060 Union Road Gastonia, NC 28056 980-522-1525

SALESPERSON	JOB	PAYMENT TERMS	DUE DATE
		Due on receipt	

QTY	DESCRIPTION	UNIT:PRICE	LINE TOTAL
	Conduit Run, Set panel, leave whip for connection		1500.00
	Wire into main panel .		
		1	
· · · · · · · · · · · · · · · · · · ·			
		SUBTOTAL	
		SALES TAX	
		TOTAL	1500

Quotation prepared by:
This is a quotation on the goods named, subject to the conditions noted below: Describe any conditions pertaining to these prices and any additional terms of the agreement. You may want to include contingencies that will affect the quotation.
To accept this quotation, sign here and return:

THANK YOU FOR YOUR BUSINESS!

The Control of the Control of the American Control of the Control



## THE NATION'S LARGEST DISTRIBUTOR OF BAUER



a manager of proprint Car Charles

210 Labrador Dr. Randleman, NC 27317

#### Quote

Order Number: 0073073

Order Date: 4/9/2019

Customer Number: 07-EQ

Sold To: UNION ROAD VOLUNTEER FD 4060 UNION ROAD Gastonia, NC 28056

Ship To: UNION ROAD VOLUNTEER FD 4060 UNION ROAD Gastonia, NC 28056

Confirm To: CHIEF HUFFSTETLER

PO#:

Terms: Credit Card

Salesperson: Ricky Lee

Quantity

1

Item Code

LEGACY 13

#### VERTECON 13CFM 6KPSI 10HP

#### VERTECON 13CFM 6KPSI 10HP

Bauer Open Vertical Compressor/Purifier configured for 13.0 scfm, 6000 psig, 4-stage compressor, 10 hp, phase motor and 67,000 scf capacity purifier, integrated purification system that meets NFPA 1989 requirements for firefighting and CGA Grade E air for SCUBA, purifier includes steel mechanical separator chamber, as well as purifier safety vent port to prevent operating system w/o cartridge. Standard with Bauer long-life, well-cooled, oil-pressure lubricated compressor block with stainless steel intercoolers, high-temperature & low oil pressure shutdowns. Mounted pressure gauges for oil, final stage and purifier. Includes PLC with touch pad controller with full color display, lighted on/off switch, hour meter, emergency stop button, safety over-time timer, motor controls/protection and UL-rated electrics.

#### **AUTO CONDENSATE DRAIN SYSTEM**

-Timed automatic drain, includes sitencer and collection reservoir and user display indicator if "full".

MTD INTERSTAGE PRESSURE GAUGES SECURUS PURIFIER MONITOR SYSTEM

- Built-in, continuous monitor for purification cartridges.
- Includes user display indicators for "safe", "high moisture", "cartridges expired" and "contact fault".
- Automatic system shutdown for faults; fail-safe (can not be over-ridden); no warm up required.
- Can extend the purifier cartridge's useable life.

1 26-SASCO-24V

PNL MOUNTED CO MONITOR 24V

1 OUTV-KIT/VERT

COMP OUTLET VLV KIT



## info@safeairsystems.com | sales@breathingair.com



QUOTE #: 0073073

Page 2 of 3

1	CE	S5.	5.	20
•	~,	TOU.	J-	40

Fill Station - Bauer - Class 2

Fill Station - Bauer - Class 2 - 2 position fill station with control valve-adjustable regulator- relief valve, manual control valve and pressure gauge for each fill position. NFPA 1901 compliant. 5500 psi fill pressure.

1	DFTM/CSCD
---	-----------

Order Only Dual Funtion top mo

**BREATHING AIR HOSE 10'** 

#### Order Only Dual Funtion top mount

1 FLUSH NO TILT FLUSH MNT PA	ANEL
------------------------------	------

5 CTX44 ELBOW, MALE CON #4MJIC X 1/4MP

4 90-UN-6000A CYLINDER, UN 6000 PSI

4 CYL-ELB-702 CGA FITTING/ELBOW FOR 6K

4 94-B996GALV UNI-STRUT PER FOOT 13/16"" GAL

#### UNI-STRUT PER FOOT 13/16" GALV

4	95-C105-93/8	CLAMPS, 9 3/8""

2 50-BA003-3E **BREATHING AIR HOSE 3'** 2 50-BA004-3E **BREATHING AIR HOSE 4'** 1 50-BA010-3E

1 REMOTAIRINTAKE REMOTE AIR INTAKE

1 /AIRTEST-SINLOL-NC LAB ON LOCALE,

1 /FREIGHT FREIGHT

2 /SHOP LABOR - NC SHOP LABOR - NC

200 /MILEAGE MILEAGE

4 /TRAVEL LABOR NC TRAVEL LABOR NO

1 FIELD LABOR SAS PER HOUR /FIELD LABOR - NC



### info@safeairsystems.com | sales@breathingair.com



QUOTE #: 0073073

Page 3 of 3

THIS QUOTE IS FOR A BAUER LEGACY 13 COMPRESSOR, 13 CFM, 6000 PSI, 10 HP SINGLE OR THREE PHASE MOTOR AND CO MONITOR.

BAUER CFS5.5-2S TWO POSITION CONTAINMENT FILL STATION WITH 4 BANK AIR CONTROL PANEL. INCLUDES BANK GAUGES AND LINE VALVES, SUPPLY GAUGE, 0-6000 PSI ADJUSTABLE REGULATOR, REGULATED PRESSURE GAUGE, (2) FILL VALVES AND (2) FILL PRESSURE GAUGES. FILL STATION IS NFPA 1901 COMPLIANT.

(4) 6000 PSI UN STORAGE CYLINDERS, 509 CU FT PER CYLINDER, WITH CGA FITTINGS AND HOSE'S TO CONNECT TO AIR CONTROL PANEL. INCLUDES UNI-STRUT & CLAMPS TO SECURE CYLINDERS TO THE WALL. UN CYLINDERS HAVE TO BE RECERTIFIED EVERY 10 YEARS.

WE WILL INSTALL A REMOTE AIR INTAKE ON THE COMPRESSOR UNIT. \*\*\*\* CUSTOMER TO HAVE A HOLE IN THE SIDE OF FIRE STATION FOR USE TO RUN THE PVC TROUGH, APPOX SIZE OF THE HOLE IS 1 1/2 TO 2 INCH PIPE. WE WILL VERIFY THE PIPE SIZE BEFORE YOU BREECH THE WALL.

PRICE INCLUDES DELIVERY & INSTALLATION OF THE EQUIPMENT ON THIS QUOTE, WE WILL PULL A ONE TIME AIR TEST AT TIME OF START-UP AND GIVE USER TRAINING AT THAT TIME.

"\*\* CUSTOMER TO PROVIDE SUITABLE ELECTRICAL SUPPLY FOR THE UNIT TO INCLUDE WALL MOUNT DISCONNECT & PIGTAIL. (PIGTAIL CONSIST OF 10 FT OF FLEX CONDUIT & 18 FT OF WIRE) SAFE AIR WILL MAKE FINAL CONNECTION TO THE UNIT.

		39,505.00
·	Less Discount:	0.00
	Freight:	0.00
	Sales Tax:	0.00
	Order Total:	39,505.00
Sales Department		
Order Acceptance	Drawnskii in reliebblijkii in saabstate on minimus juga ja julija.	<del>volusiin kastiin 2 die 1220 volus</del> e 344
Sign: Date:		
itie: PO#:		